QUOTATION

Name of work:-Providing 12 Nos.of 5 amp & 8 Nos of 15 Amp Power points in the PG Lab of Sustainable Energy Engineering Department.

S.No.	Description	Qty.	Unit_	Rate (in words & Figures)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.	S			
a)	3 x 1.5 Sq.mm	25.00	Mtr.		
b)	3 x 4 Sq.mm	24.00	Mtr.		
2	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a)	5/6 Amp switch	9.00	Nos.		
b)	15/16 Amp. switch	4.00	Nos.		
c)	3 Pin 5/6 Amp. socket outlet	9.00	Nos.		
d)	6 Pin 15/16 Amp. socket outlet.	4.00	Nos.		
e)	Blanking plate	3.00	Nos.		
3	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
a)	3 module	2.00	Nos.	9	
b)	4 module	3.00	Nos.		
	S/F following modular base & cover plate on existing modular metal boxes etc. as reqd.				
a)	3 module	2.00	Nos.		
b)	4 module	3.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (in words & Figures)	Amount
10	5 4 14	4.00	NI		
c)	6 module	4.00	Nos.		
5	Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with		300	B	50-
	connections, testing and commissioning etc. as reqd.				
a)	Single Pole	5.00	Nos.		
b)	Triple pole & Neutral	5.00	Nos.		
6	Supplying and fixing DP sheet steel enclosure on surface/ recess along with 25/32 A 240 V "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	5.00	Nos.		
	1				
7	Supplying and fixing TP sheet steel enclosure on surface/ recess along with 16/25/32 A 415 V "C" curve TP MCB complete with connections, testing and commissioning etc. as required.	5.00	Nos.		
8	Supplying and making indoor end termination with brass compression gland, aluminum lugs for following size of PVC insulated & PVC sheathed/XLPE aluminum cable of 1.1kV grade as reqd.	а			
a)	3-1/2x25 sq.mm.	12.00	Nos.		
b)	3-1/2x35 sq.mm.	10.00	Nos.	*	
9	Providing and fixing following sizes of PVC casing and capping on surface as reqd.	*:		I Ā	
a)	20 x 12 mm	30.00	Mtr.		
10	Supplying, installation DLP minitrunking 32mm x 20mm and accessories white-system with independent coverwithout central partion etc. as reqd.				

S.No.	Description	Qty.	Unit	Rate (in words & Figures)	Amount
a)	Mini- trunking	13.00	Mtr.		
11	Providing and fixing DLP plastic trunking of size 105 mm x 50 mm without cover on surface as reqd.	2.87	Mtr.		
12	Providing and fixing 85 mm width flexible cover of DLP plastic trunking. (size 105 mm x 50 mm.)	2.00	Mtr.		

Total Rs.

अधिशाषी अभियंता (वि०) E.E. (Elect. संतनिवविव, भावप्रीव संस्थान, कानपुर I W D. L.I.T., Kanpur