

## QUOTATION

Name of work -:Replacement of defective LAN wire from U-26 to H. No. 340 Type- III as per enclosed DOIP forms 101 requested by Computer Centre with all allied works as required in the campus at IIT Kanpur.

S.No	DESCRIPTION	Qty	UNIT	RATE (In words & Figures)	Amount
1	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep)and re-filling etc as required				
a)	50 mm	8.00	Mtr.		
2	Supply and laying of HDPE pipe ISI mark of 32 mm (8Kg / cm <sup>2</sup> ) size outer dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a)	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	65.00	Mtr.		
b)	In Pipe	8.00	Mtr.		
c)	In open duct	2.00	Mtr.		
3	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	10.00	Mtr.		
4	Laying UTP cable enhanced cat 5/ cat 6/ fiber cable in existing steel conduit pipe/GI pipe raceway/ HDPE pipe / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	170.00	Mtr.		

7

S.No	DESCRIPTION	Qty	UNIT	RATE (In words & Figures)	Amount
------	-------------	-----	------	------------------------------	--------

5	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. ( box and cover plate will be supplied by dept.)	1.00	Nos.		
---	---	------	------	--	--

Total Rs.

७  
 अधीक्षक अभियंता / इ. त्त.  
 खासियत (अ. त्त.)  
 भारतीय प्रशासन, काशी  
 I.T., Kashi  
*(Signature)*

*(Signature)*  
 21/02/23