

## QUOTATION

Sub: Providing LED postop lantern on the approach path from NWTF building to the newly constructed workshop.

S.N.	Description	Qty.	Unit	Rate	Amount
1	Supplying & Laying of one no. XLPE cable aluminium conductor steel armoured cable of size 2x6sqmm, grade 1.1kV in following manners.				
a	In Ground I/c excavation, sand cushioning protective covering, refilling of earth as reqd.	50.00	Mtr.		
b	In existing Pipe	10.00	Mtr.		
c	In existing open duct	5.00	Mtr.		
2	Erection of steel pole tubular in cement concrete 1:3:6 ( 1 cement : 3 coarse sand: 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts etc. as reqd	3.00	Nos.		
3	S&F, connecting and commissioning looping type cable end control box with MS sheet of 16 SWG of size 200 mm x 200 mm x 125 mm having 1 no. 6amp to 32 amp SPMCB 250 volt and 2 nos. brass neutral link square rod 6 way and fixed on 5 mm thick bakelite sheet. Box shall have almirah type hing and panel key type lock front door duly painted with earthing strud etc. complete as required.	3.00	Nos.		
4	Supply & laying of HDPE pipe ISI mark of size 25mm inner dia, 8Kg / cm <sup>2</sup> and minimum 2mm thick I/c cartage loading & unloading etc. as reqd.				
a	Fixing on surface with MS clamp	7.00	Mtr.		
5	Providing and fixing 6 SWG dia. GI wire on surface or in recess for loop earthing alongwith the existing surface / recessed conduit / submain wiring / cable as required.	130.00	Mtr.		
6	Supplying and drawing following sizes of FR-LSH PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	2 x 1.5 Sqmm.	9.00	Mtr.		
	S/F testing commissioning of street light Luminures. Endura cityliner neo type 48W LED				
7	LHETAXU7PN6W048, die-cast aluminium IP66 type make:philips or its equivalent, on the existing street light pole complete as required.	1.00	Nos.		

S.N.	Description	Qty.	Unit	Rate	Amount
------	-------------	------	------	------	--------

8	Supplying,fixing,testing commissioning of garden light 40W LED postop lantern Luminures for 360 degree indirect light. Cat noLPTO- 40/CDL, make:Crompton greaves or its equivalent, on the existing pole complete as required.	5.00	Nos.		
---	--	------	------	--	--

**Total Rs.**

  
 राघवेंद्र सिंह  
**RAGHVENDRA SINGH**  
 अधिकारी, कार्यलय (विद्युत) E.E. (Elect.)  
 जल संयंत्र, रायचूर, रायचूर, जयपुर  
 305 001, राजपुत्र  
