


QUOTATION

Sub: Supplying & laying cable for providing power supply to newly constructed Workshop near NWTF Building.

S.N.	Description	Qty.	Unit	Rate(Rs.)	Amount
1	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc as reqd.				
a	200 mm X 250 mm X 60 mm deep	2.00	Nos.		
2	Providing and fixing following rating and breaking capacity four pole 415V 50Hz MCCB in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc as required.				
a	200 Amp, 25 KA	1.00	Nos.		
3	Providing and fixing spreader terminal set suitable for 200 amp MCCB etc as required.	2.00	set		
4	S&F connecting and commissioning independent mounting of MCCB enclosure suitable for 200 amp MCCB's in surface/recess I/c cutting the wall and making good the same in case of recessed etc as reqd.	1.00	Nos.		
5	Supplying & Laying of one no. PVC insulated & PVC sheathed aluminium conductor steel armoured cable of size 3-1/2x150 sqmm 1.1kV grade .				
a	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	37.00	Mtr.		
b	On surface with MS clamp	8.00	Mtr.		
6	Supplying and making end termination with brass compression gland with aluminium lugs for following size of PVC insulated & PVC sheathed/XLPE aluminium cable of 1.1kV grade as reqd.				
a	3-1/2x 150 sqmm	4.00	Nos.		

S.N.	Description	Qty.	Unit	Rate(Rs.)	Amount
7	Structure steel work riveted, bolted or welded in built up sections, truses and framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	5.00	Kg.		

Total Rs.


राघवेंद्र सिंह
RAGHVENDRA SINGH
अधिराजी अभियंता (वि०) E.E. (Elect.)
संवि०वि०, मा०प्रौ० संस्थान, कानपुर
S.W.D., I.T., Kanpur