

## QUOTATION

Sub: Providing power points & internet points for work station of 20 Nos. computer tables at Aerosol Building.

S.N.	Description	Qty.	Unit	Rate(Rs.)	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	3 X 1.5 Sq.mm	50.00	Mtr		
b	3 X 2.5 Sq.mm	150.00	Mtr		
c	3 x 4 Sq.mm	50.00	Mtr		
2	Supply and drawing PVC insulated copper conductor (Flexible) 3 core round cable 2.5 Sq.mm for connection of equipments / exhaust fan/AC & other work as reqd.	10.00	Mtr.		
3	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as reqd.				
a	20 mm	10.00	Mtr		
b	25 mm	75.00	Mtr		
c	32 mm	15.00	Mtr		
4	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.	15.00	Mtr.		
5	Supply and fixing of following items for plastic trunking accessories suitable for size 32 mm x 20 mm				
a	End cap	2.00	Nos.		
b	Internal angle/ External angle	2.00	Nos.		
c	Changeable flat angle	2.00	Nos.		
d	Flat Junction	2.00	Nos.		

S.N.	Description	Qty.	Unit	Rate(Rs.)	Amount
6	Providing and fixing DLP plastic trunking of size 105 mm x 50 mm without cover on surface as reqd.	25.00	Mtr.		
7	Providing and fixing 85 mm width flexible cover of DLP plastic trunking. (size 105 mm x 50 mm.)	25.00	Mtr.		
8	Supply and fixing of following items for plastic trunking accessories suitable for size 105 mm x 50 mm.				
a	End cap	5.00	Nos.		
b	Internal angle.	1.00	Nos.		
c	External angle	1.00	Nos.		
d	Flat Junction	2.00	Nos.		
e	Changeable flat angle	2.00	Nos.		
f	Separation partitions	20.00	Mtr.		
g	cover joint	5.00	Nos.		
h	Base joint	10.00	Nos.		
9	S & F of following size of steel flexible pipe alongwith the accessories on surface etc as required.				
a	20 mm	2.00	Mtr.		
b	25 mm	2.00	Mtr.		
10	Supplying and fixing following modular switch/socket on the existing modular plate & switch box/ DLP plastic trunking including connections but excluding modular plate etc as reqd.				
a	5/6 amps switch	75.00	Nos.		
b	15/16 amps switch	10.00	Nos.		
c	3 pin 5/6 amps socket outlet	75.00	Nos.		
d	6 pin 15/16 amps socket outlet	10.00	Nos.		
e	Blanking Plate	1.00	Nos.		

S.N.	Description	Qty.	Unit	Rate(Rs.)	Amount
11	Supplying and fixing following Modular GI/plastic base & cover plate on existing modular metal boxes/DLP plastic trunking etc. as required.				
a	3 Module	20.00	Nos.		
b	6 Module	20.00	Nos.		
12	Supplying and fixing following Module Plastic box for fixing modular switches/sockets in surface/recess etc as required.				
a	3 Module	15.00	Nos.		
b	6 Module	5.00	Nos.		
13	Fixing, Internet Box of size 75mm x 75mm x 40 mm including brass screw on surface / recessed as reqd.	23.00	Nos.		
14	Drawing of computer network cable/ PVC insulated flexible cooper/ Aluminium single core cable of size 1.5sqmm to 25 sqmm/ telephone cable upto 10 pair in existing pipe / casing and capping as reqd including numbering the wires at both the ends.	500.00	Mtr.		
15	Supply fixing connecting & commissioning of 5 Amp. 3 pin Plug top as reqd.	1.00	Nos.		
16	Supply fixing connecting & commissioning of 15 Amp. 3 pin Plug top as reqd.	1.00	Nos.		

**Total Rs.**

  
 रावी वेंद्रा सिंह  
 RAVI VENDRA SINGH  
 अधिकारी (गैर आर. टी.) (Elect.)  
 राजस्थान विद्युत निगम, जयपुर  
 J.W.D., D.L., Jaipur  
