


QUOTATION

Sub: Repair and Painting of damage/defective geyser including replacement of defective parts installed in Girls/Boys Hostels.

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
1	Dismantalling inner tank of geyser , removal of deposited scales with descaling solution, repairing leakage and leak testing after repair with hydraulic pressure machine complete as required.	12.00	Nos.		
2	Repairing of apparatus plate for water heater geysers including cutting, brazing and replacement of defective fittings complete as reqd.	4.00	Nos.		
3	Repairing outer body of geyser (including cutting,removing damage portion ,welding/brazing /patch works etc.) complete as reqd.	10.00	Nos.		
4	Supply and Fixing outer shell (MS sheet) of suitable shape and size for Geyser 50 Ltr capacity.(old damage body shall be retained by the contractor)	2.00	Nos.		
5	Supply and Fixing glass wool insulation for 50/70 ltrs geyser after removing defective insulation etc. complete as required.	2.00	Nos.		
6	Painting of geysers up to 50 litres capacity (inner & out side) after primer complete as required.	12.00	Nos.		
7	Cartage to and fro of geyser from site to work shop and back including loading/ unloading complete as required..	12.00	Nos.		
8	Supply,fixing,connecting and commissioning of heating element 2kw,thermostat,thermal cut,indication lamp with 3 core power cable up to 1.5 meter length in existing/ repaired geyser up to 50lits capacity complete as required	12.00	Nos.		

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
9	Installation, testing and commissioning electrical back-up 3Kw ISI marked including heating element, thermoestate connecting etc as required complete.	20.00	Nos.		
10	Supply and Fixing of geyser of following capacity complete as required (make racold Platinum or its equivalent make).				
a)	50 litrs. Capacity	2.00	No.		
11	Supply of electrical back-up 3Kw ISI marked complete as reqd.	30.00	Nos.		
12	Supply of following accessories for geyser complete in all as required.				
a)	CP nut with washer	30.00	Pairs		
b)	Indicator	10.00	Pairs		
c)	Copper pipe	15.00	Mtr		
Total Rs.					


 विनय कुमार तिवारी
 VINAY KUMAR TIWARI
 अधीक्षक अभियंता (वात) E.E. (A.C.)
 संचालक, भारतीय संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur