

QUOTATION

Sub: Providing & fixing of angle iron frame with canopy, servicing of cold room and rewinding of ductable AC motor installed at Health centre, VH, Hall VIII & 4i-lab etc.

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
1	Supply & Fixing of Angle iron frame of 25/32 mm, thickness 5 mm for mounting of outdoor unit size, duly painted and finished with GI/ fiber canopy and vibration pad if required complete etc. as reqd				
a)	Floor Mounted (Upto 2.0 Capacity)	13.00	Nos,		
b)	Wall Mounted (Upto 2.0 Capacity)	2.00	Nos,		
c)	Canopy (Shed)	8.00	Nos,		
2	Supply and fixing ball bearing of following size including dismantling of defective bearing complete as reqd. (Make NBC/SKF)				
a)	6205 ZZ	2.00	Nos.		
3	Servicing of cold room i/c cleaning of condenser coils by removing dust & washing with fresh water, lubricating the fan motor, i/c re-fitting of cold room with plumbing work by using auto wire, PVC, tape, thimbles m/c screws, washers, nut, bolts etc. as reqd. (complete)	1.00	Nos.		
4	Rewinding of three phase electrical motor of following capacity including the supply of copper winding wire (Milan make) varnishing using Dr. Beck's Varnish, testing, assembling and commissioning as reqd (Old burnt wire shall be retained by the contractor) complete as reqd.				
a)	3 HP, 3 phase	1.00	Job		
Total Rs.					