

QUOTATION


Sub:- Making of extra network points for installation of Wi-Fi access points for proper Wi-Fi coverage at under construction CEM building.

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
--------	-------------	-----	------	------	--------

(In words & Figures)

- | | | | | | |
|------|--|--------|-------|--|--|
| 1 | Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required. | | | | |
| 1.01 | 25 mm | 400.00 | Metre | | |
| 2 | Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept) | 500.00 | Meter | | |
| 3 | Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.) | 25.00 | Nos. | | |

Total Rs.


सहायक अभियंता (वि)/एम.एम.सी.
संरचना, नगरीय विकास विभाग
I.W.D., E.H.E. Karapur
