


QUOTATION

Name of work : Providing additional street lights in pathway between NAF & New AC plant.

S.No	Description	Qty	Unit	Rate	Amount
				(In words & Figures)	
1	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
a	Double pole	1.00	Nos.		
2	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.				
a	20 mm	50.00	Mtr.		
3	Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required.	4.00	Each		
4	Supplying and fixing of 32 mm dia X 2.00 metres long G.I. pipe (medium class) bracket for mounting of fluorescent / HPMV / HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint etc. as required.	4.00	Nos.		
5	Supplying and fixing DP sheet steel enclosure on, surface/ recess along with 25/32 A 240 V "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	1.00	Each		
6	Supplying and fixing 25 mm dia MS flexible pipe with PVC coating along with all ancillaries and accessories like coupler etc. as required.	5.00	Nos.		

S.No	Description	Qty	Unit	Rate	Amount
(In words & Figures)					
7	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a	2 X 6 sq. mm (19mm)	2.00	Each		
8	Supplying and drawing of following sizes of FRLSH PVC insulated copper conductor, 3 core round cable of following size in the existing surface/ recessed steel/ PVC conduit as required.				
a)	1.5 Sqmm	65.00	Mtr.		
9	Supply , Fixing testing commissioning of street light Luminures fitting 36W . FREEDOM NEO LED streetlight made up of pressure die cast housing with toughened glass and high power LEDs with option of secondary optic with IP65 protection type make: Cropmton greaves on the existing street light pole complete as required.	4.00	Nos.		
10	Supplying & Laying of one no. XLPE cable aluminium conductor steel armoured cable of size 2x6sqmm, grade 1.1kV in following manners.				
a	Fixing on surface with MS clamp	10.00	Mtr.		
Total Rs.					<hr/> <hr/>


 अधिकारी अधिकारी (सि) E.E. (A/C)
 कृष्णापट्ट, नागरी सेवाएं विभाग
 T.W.D., U.T. Kavaratti