

QUOTATION

Sub:- **Replacement of defective & damaged DB & Wire ect. in L.H.C-19.**

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
1.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	1 x 70 sq.mm.	12.00	Meter		
2.00	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	0.50	Meter		
3.00	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
3.01	85 mm flexible cover	0.50	Meter		
3.02	End cap	2.00	Nos.		
4.00	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
4.01	6 /10/16 Sq.mm.	24.00	Nos.		
4.02	70 Sq.mm.	12.00	Nos.		
5	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 A tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs and incomer) as required . (Note : Vertical type MCB TPDB is normally used where 3 phase outlets are required.)				
5.01	12 way (4 + 36), Double door	1.00	No.		

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(In words & Figures)					

6.00 Supplying and fixing following rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.


6.01 Triple pole (40A-63A) 6.00 Nos.

7.00 Dismantling concealed & damaged DB/TPN Switches/starter/ loose wire boxes along with all accessories and depositing the same in the sectional store repairing the damages as reqd complete. 1.00 Nos.

8.00 Supplying and fixing 250 Amp rating, 240/415 volts, suitable for inductive load of following Extended spreaded terminals in the existing MCCB complete with connections, testing and commissioning etc. as required. 1.00 Set

9 Supplying and fixing single pole blanking plate in the existing MCB DB complete etc. as required. 26.00 No.

Total Rs. _____


 अधिशासी अभियंता (वि०) ए.ए. (Elect.)
 संचिका, गांधी संस्थान, कानपुर
 I.W.D., I.L.T., Kanpur
 2