

QUOTATION

Name of work -: Providing and laying of LAN wire in NL-2 101 as per enclosed request from IITK.

S.No	DESCRIPTION	Qty	UNIT	RATE	Amount
(In words & Figures)					
1	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	38.00	Meter		
2	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
2.1	internal / external angle	1.00	Nos.		
2.2	changeable flat angle	10.00	Nos.		
2.3	flat junction	4.00	Nos.		
3	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	19.00	Meter		
3.1	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
3.2	85 mm flexible cover	18.50	Meter		
3.3	End cap	5.00	Nos.		
3.4	flat angles	5.00	Nos.		
3.5	Joints for 85mm width cover	5.00	Nos.		
3.6	base joints	10.00	Nos.		
4	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required				

S.No	DESCRIPTION	Qty	UNIT	RATE	Amount
(In words & Figures)					
4.1	32 mm	8.00	Meter		
5	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	30.00	Nos.		
6	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	1500.00	Meter		
7	Fixing of Network rack on steel fashtner including cartage from store to site as reqd complete.	1.00	Nos.		

Total Rs.


 अधिकांश प्रियवता (ईको) E.E. (Elect.
 सोनिाबड, माडग्री संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur

