


QUOTATION

Name of work:- Repairing of 11KV HT cable going from HT panel to Transformer-1 at Substation No.4.

S.No.	Description of item	Qty	Unit	Rate	Amount
(In words & Figures)					
1	Supplying and making straight through cable jointing with heat shrinkable jointing kit complete with all accessories including ferrules suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required :				
a.	120-185 sq. mm	2.00	Each		
2	Supplying and Laying of one No. PVC insulated/PVC sheathed 6.6 KV(UE) 11kV(E) grade XLPE HT power cables (heavy duty) size. 185Sqmm, aluminium conductor, steel armoured cable as per , IS:7098 (Part-II/2011) as reqd.				
a	In pipe	5.00	Mtr		
b	In open duct	10.00	Mtr		
3	Locating fault in the cable lines with fault locator machine etc and rectifying removing & restoring the same and making good the damages etc as required.	1.00	Nos.		
4	Lifting removing cable exceeding 95 sq.mm. but not exceeding 185sq.mm. size from trench/clamps, making role & depositing the same in store l/c cartage.as per requirement.	15.00	Mtr		
Total Rs.					<hr/> <hr/>


जबिसापी अनियन्दा (विद्युत) E.E. (Elect.
संनिविदा, वायुमार्ग संस्थान, कानपुर
I W.D., I.L.T., Kanpur