


QUOTATION

Name of work:- Repairing of main service cable of NCC building and other associated works.

S.N	Description of item	Qty	Unit	Rate	Amount
				(In words & Figures)	
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.				
a	Above 35 sq. mm and upto 95 sq. mm	50.00	Mtr		
2	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required.				
a	Above 35 sq. mm and upto 95 sq. mm	5.00	Mtr		
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required.				
a	Above 35 sq. mm and upto 95 sq. mm	5.00	Mtr		
4	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a	3½ X 95 sq. mm	2.00	Each		
5	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.				
a	125 A,36KA,FPMCCB	1.00	Each		
6	Locating fault in the cable lines with meggar etc and rectifying removing & restoring the same and making good the damages etc as required.	2.00	Nos.		

S.N	Description of item	Qty	Unit	Rate	Amount
				(In words & Figures)	
7	Lifting removing cable exceeding 35 sq.mm. but not exceeding 95sq.mm. size from trench/clamps, making role & depositing the same in store l/c cartage.	100.00	Mtr		
8	Dismantling and refixing brass compression type gland up to 400 sq. mm. cable	4.00	Nos		
9	Fixing & connecting 1 phase/3 phase temporary service connection from supply source to the desired place for lead of 50 mtr and dismantling the same from the source l/c cartage to & fro from store (extension board & cable/wire will be supplied by the dept.)	1.00	Nos		
10	Digging cable trench for taking out cable and refilling , watering ,ramming the sameafter taking out cable as reqd complete.	20.00	Mtr		

Total Rs.


 अधीनस्थ अधिकारी (वि.) E.E. (Elect)
 संचालक विभाग, जल संचयन, काठगढ़
 I.W.D., I.L.T., Kathgarh
