

## QUOTATION


Sub Repairing/replacement of defective electrical items in BSBE Lab 9, SL 207, WL 303C & D CEREMIC LAB, BSBE Corridor and different labs and offices in academic area on complaint basis.

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 2.5 sq. mm	25.00	Metre		
b	3 x 6 sq. mm	38.00	Metre		
c	3 x 10 sq.mm.	50.00	Meter		
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	15/16 A switch	6.00	No.		
b	6 pin 15/16 A socket outlet	6.00	No.		
3	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	6 Module	3.00	No.		
4	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
a	Triple pole 5 A to 32 A	4.00	No.		
b	Triple pole and neutral 5 A to 32 A	2.00	No.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
c	Triple pole (40A-63A)	1.00	Nos.		
d	Four Pole (40A-63A)	1.00	Nos.		
5.00	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
a	6 /10/16 Sq.mm.	12.00	Nos.		
6.00	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required				
a	32 mm	5.00	Meter		
7.00	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required/ complete.	28.00	Meter		
8.00	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	20.00	Meter		
9.00	Locating fault <b>in wiring</b> rectifying removing & restoring supply the same & making good the damages etc as reqd.	5.00	Nos.		
10.00	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	26.00	Nos.		
11.00	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a	6 Module	3.00	Nos.		

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
12.00	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	2.00	Nos.		
13.00	Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete.				
a	20 watt ESENTIAL PHILIPS or equivalent Tube inplace of 36/40 W FL tube	4.00	Nos.		
14.00	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffusser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
a	12 watt resess mounting LED light fixture	24.00	Nos.		
b	36 watt recess mounting LED light fixture 600 x 600 mm	2.00	Nos.		
15.00	Supplying and fixing Infrared sensors 400 W 2 module suitable for following Lighting complete with connections, testing and commissioning etc. as required.	1.00	Nos.		

**Total Rs.**

  
 श्री. अ. वि. वि. (पि) / ए. ए. (डिप्टी)  
 इंजीनियर, एम. टी. संस्था, काशी  
 I.W.D., I.T. Kanpur

*Deat*