

QUOTATION

Name of work:-Drawing of fiber cable in DJAC building with allied works and providing UPS & raw power point near network racks in Earth science (ESB-3) & old core lab extension building as per request by computer centre in the campus at IIT Kanpur.

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
1.1	3 x 1.5 Sq.mm..	180.00	Mtr.		
2	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
2.1	5/6 Amp switch	8.00	Nos.		
2.2	3 Pin 5/6 Amp. socket outlet	8.00	Nos.		
3	S/F following modular base & cover plate on existing modular metal boxes etc. as				
3.1	3 module	8.00	Nos.		
4	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep)and re-filling etc as required				
4.1	50 mm	10.00	Mtr.		
5	Supplying and installing following size of perforated painted with powder coating M.S. cable trays with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with M.S. suspenders including bolts & nuts, painting suspenders etc as required.				
5.1	300 mm width X 50 mm depth X 1.6 mm thickness	90.00	Mtr.		



S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
6	Supplying and fixing following size/ surface mounting plastic box as required.make havells OR equivalent approved make.				
6.1	3 module	8.00	Nos.		
7	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.				
7.1	Mini- trunking	50.00	Mtr.		
7.2	End cap left or right	4.00	Nos.		
7.3	Internal/ external angle	2.00	Nos.		
7.4	Flat angle	3.00	Nos.		
7.5	Flat junction	2.00	Nos.		
8	Laying UTP cable enhanced cat 5/cat 6 cable/fiber optical cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	250.00	Mtr.		
9	Supply and fixing of following items for plastic trunking accessories suitable for size 105 mm x 50 mm.				
9.1	Separation partitions	90.00	Mtr.		

Total Rs.

8
 सर्वोच्च न्यायालय/उच्च
 न्यायालय (उ.प्र.)
 न्यायाधीश सचिवालय, काठमाडौं
 I.I.T., Kengeri
 Deelu