


QUOTATION

Name of work : Providing light points for Automatic Urinal Flusher in common toilets (4 No's) of main Auditorium.

S.No.	Description	Qty.	Unit	Rate	Amount
				(in words & Figures)	
1	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required.				
a)	Group A	25.00	point		
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a)	5/6 Amp switch	5.00	each		
3	Supplying, fixing , testing & commissioning of 18W LED. trim cosmo square surface mountaed LED panel with premium diffuser with longer life and less maintenance. with all fixing accessories as required complete LED make Havells or its equivalent make etc as reqd	7.00	Nos.		

Total Rs.


उपनिवेश / S.E.
संविधि (I.I.T.)
भाषी संस्थान, कापुर
I.I.T., Kanpur



