

## QUOTATION

Sub:- Providing and fixing power & network points in Fire studies lab.( Old Kanzi House)

SL No.	DESCRIPTION	QTY	UNIT	RATE (Rs) Words & Fig.	AMOUNT
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 2.5 sq. mm	10.00	Metre		
1.02	3 x 4 sq. mm	45.00	Metre		
2	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	5.00	Meter		
3	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partition etc. as required complete.	18.00	Meter		
4	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
4.01	85 mm flexible cover	16.00	Meter		
4.02	End cap	3.00	Nos.		
4.03	Internal angles- adjustable from 80°-100°	2.00	Nos.		
4.04	external angles- adjustable from 60°-120°	1.00	Nos.		
4.05	flat junction	1.00	Nos.		
4.06	flat angles	1.00	Nos.		
4.07	separation partitions	12.00	Meter		
4.08	Joints for 85mm width cover	6.00	Nos.		
4.09	base joints	16.00	Nos.		
5	S & F following size of steel flexible pipe along with the accessories on surface etc				
5.01	32 mm	5.00	Meter		
6	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.				
6.01	32 mm	60.00	Metre		

Sl No.	DESCRIPTION	QTY	UNIT	RATE (Rs) Words & Fig.	AMOUNT
7	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc.				
7.01	3 module	10.00	Nos.		
7.02	6 module	10.00	Nos.		
8	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
8.01	6 A switch	10.00	No.		
8.02	20 A switch	20.00	No.		
8.03	6 A pin 2/3 pin socket outlet	10.00	No.		
8.04	6/16 A 3 pin socket outlet	20.00	No.		
9	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	400.00	Meter		
10	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. ( box and cover plate will be supplied by dept.)	10.00	Nos.		
<b>Total Rs.</b>					

*[Handwritten signature]*

6  
अधीक्षक अभियन्ता / S.E.  
सि.वि.वि. (I.W.D.)  
सामाजिक संस्थान, कांपुर  
(I.T., Kanpur)  
*[Handwritten signature]*