

QUOTATION

Sub:- Repairing and raising of two no. Electrical chamber at CEAF Building.

SL No.	DESCRIPTION	Qty	UNIT	RATE	AMOUNT
				(In words & Figures)	
1	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	3.25	cum		
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in				
a	Cement mortar 1:6 (1 cement : 6 coarse sand)	0.95	cum		
3	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete				
a	125 mm	4.00	Nos.		
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	40.25	Kg.		
5	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.				
a	Using M.S. angels 40x40x6 mm for diagonal braces	5.30	Sqm.		
6	12 mm cement plaster of mix				
a	1:6 (1 cement: 6 coarse sand)	4.50	Sqm.		



SL No.	DESCRIPTION	Qty	UNIT	RATE	AMOUNT
--------	-------------	-----	------	------	--------

(In words & Figures)

- 7 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade
- a Two or more coats on new work 11.60 Sqm.

Total Rs.


 अधीक्षक अभियन्ता (A.E.)
 सतलोकविठो (A.W.D.)
 भाद्रपूर संस्थान, कानपुर
 I.I.T., Kanpur


