

QUOTATION


Name of work: Providing additional 5A & 15A plug points and light, fan in Room 104B at KD Building, and 3 floor pantry at RM building in Academic area as per requested by User with all allied works as required in the campus at IIT Kanpur.

S. No.	Description	Qty.	Unit	Rate	Amount (Rs.)
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
a)	Group C	6.00	Point	924.96	5549.78
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a)	3 x 1.5 sq. mm	30.00	Metre	98.29	2948.71
b)	3 x 4 sq. mm	35.00	Metre	213.13	7459.71
3	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a)	5/6 A switch	9.00	No.	106.57	959.11
b)	15/16 A switch	2.00	No.	161.40	322.81
c)	3 pin 5/6 A socket outlet	2.00	No.	126.23	252.45
d)	6 pin 15/16 A socket outlet	2.00	No.	203.82	407.65
e)	Blanking Plate	1.00	No.	41.39	41.39
f)	two module stepped type fan regulator	2.00	No.	381.78	763.56
4	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a)	3 Module	2.00	No.	156.23	312.46
b)	8 Module	1.00	No.	218.31	218.31
c)	12 Module	1.00	No.	281.42	281.42
5	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a)	3 Module	2.00	Nos.	341.43	682.86
b)	8 Module	1.00	Nos.	406.61	406.61
c)	12 Module	1.00	Nos.	743.90	743.90
6	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	40.00	Mtr	225.55	9022.01
7	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
a)	End cap	6.00	Nos.	147.95	887.72
b)	internal / external angle	6.00	Nos.	140.71	844.26
c)	changeable flat angle	3.00	Nos.	118.98	356.95
d)	flat junction	3.00	Nos.	140.71	422.13
8	S & F following size of steel flexible pipe along with the accessories on surface etc as required				
a)	25 mm	7.00	Mtr	85.87	601.12
9	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
a)	6 A switch	1.00	No.	191.41	191.41
b)	20 A switch	2.00	No.	326.94	653.89

S. No.	Description	Qty.	Unit	Rate	Amount (Rs.)
c)	6 A pin 2/3 pin socket outlet	1.00	No.	216.24	216.24
d)	6/16 A 3 pin socket outlet	2.00	No.	413.85	827.71
10	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
a)	3 module	1.00	Nos.	292.80	292.80
b)	6 module	1.00	Nos.	381.78	381.78
11	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
a)	1 X 20W Box type LED tube with fitting	2.00	Nos.	982.90	1965.80
12	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.	102.43	204.86
13	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept) (1, 2 & 3 Run of cable)	70.00	Mtr	23.80	1665.76
	Total Estimated Rs. (i/c GST)				39885.14
	Say Rs. (i/c GST)				39885.00
	Quoted Percentage Above/below				
	Quoted Amount Rs. (i/c GST)				

Bidder Signature & Date

Bidder Seal


 तालकुरी केशवदास
 TALI KURI KESAVADAS
 अधिकारी अभियंता (वि.सं.)
 Executive Engineer (Elect)
 सि.वि.वि. मा.अ. अक्षांश, वस्ती
 I.W.D., T.I.T. Karapur
