


QUOTATION

Name of work :- Replacement of damaged LAN wire of Houses No 226 Type-II & 4068 Type-IV in the campus .

S.No	DESCRIPTION	Qty	Unit	Rate	Amount
1	S & F of following size of steel conduit along with the accessories in surface/recess I/c painting in case of surface conduit or cutting the wall and making good the same in case of recessed conduit. as reqd.				
1.1	25 mm	10.00	Mtr.	286.00	2860.00
2	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	3.00	Nos.	102.00	306.00
3	Drawing of optical cable enhanced cat 5/cat 6/telephone/ networking /power cable in existing steel conduit pipe/GI /HDPE pipe including numbering of networking wire from room to rack as reqd.	207.00	Mtr.	24.00	4968.00
4	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
4.1	25 x 16 mm	40.00	Mtr.	79.00	3160.00
5	Supply and laying of HDPE pipe ISI mark of 32 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
5.1	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	108.00	Mtr.	476.00	51408.00
5.2	In pipe	8.00	Mtr.	87.00	696.00
5.3	In open duct	2.00	Mtr.	76.00	152.00
5.4	On surface with MS clamp	1.00	Mtr.	104.00	104.00
6	Supplying and embedding following dia G.I. pipe (medium class) in pole collar/ foundation (during casting) for cable entry including bending the pipe to the required shape complete as required.				
6.1	40 mm dia	8.00	Mtr.	620.00	4960.00
	Total Estimated Rs.(i/c GST)				68614.00
	Quoted Percentage Above/Below				
	Quoted Amount Rs (i/c GST)				

Bidder Signature & Date

Bidder Seal


TALLURI KESAVADAS
 अधिकायी अभियंता (विद्युत)
 Executive Engineer (Elect)
 स. वि. वि. वा. प्र. म. स. क. कानपुर
 I.W.D., I.I.T. Kanpur