

QUOTATION

Sub:-	Providing and fixing additional lights and power points at ESB-3-213 etc and other associated works.				
SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1.00	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS/HFFR PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS/HFFR PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
1.01	Group C	5.00	point	1053.00	5265.00
2.00	Supplying and drawing following sizes of FRLS/HFFR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
2.01	3 x 1.5 sq. mm	24.00	Meter	103.00	2472.00
2.02	3 x 2.5 sq. mm	22.00	Meter	147.00	3234.00
3.00	Supply and fixing of 32 x 20 mm DLP mini-trunking white-system with independent cover etc. as required complete.	7.00	Meter	329.00	2303.00
4.00	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
4.01	End cap	2.00	Nos.	188.00	376.00
4.02	internal / external angle	2.00	Nos.	176.00	352.00
4.03	changeable flat angle	2.00	Nos.	217.00	434.00
5.00	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
5.01	18 watt recess 300 x 300 mm mounting LED light fixture	2.00	Nos.	1321.00	2642.00
5.02	36 watt surface mounting LED light fixture 600 x600 mm	3.00	Nos.	3651.00	10953.00
5.03	20 watt batten type LED light fixture	1.00	Nos.	660.00	660.00
6.00	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
6.01	5/6 A switch	4.00	No.	120.00	480.00
6.02	3 pin 5/6 A socket outlet	4.00	No.	135.00	540.00

7.00	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
7.01	3 Module	1.00	No.	173.00	173.00
7.02	6 Module	2.00	No.	205.00	410.00
8.00	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
8.01	3 Module	1.00	Nos.	342.00	342.00
8.02	6 Module	2.00	Nos.	387.00	774.00
9.00	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
9.01	2 module	2.00	Nos.	423.00	846.00
10	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
10.01	6 A switch	3.00	No.	200.00	600.00
11.00	S & F following size of steel flexible pipe along with the accessories on surface etc as				
11.01	20 mm	10.00	Meter	60.00	600.00
	Total Estimated Rs. (i/c GST)				33456.00
	Quoted Percentage Above/ Below				
	Quoted Amount Rs.(i/cGST)				

Bidder Signature & Date

Bidder Seal


 ताल्लुरि केशवदास
 TALLURI KESAVADAS
 अधिशाही अभियंता (विद्युत)
 Executive Engineer (Elect)
 सं.वि.वि. भा.प्रौ. संस्थान, कांठपुर
 I.W.D., I.I.T. Kanpur
 30/26