

QUOTATION

Sub:-	Providing and making additional power points at BSBE Lab-18.				
SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1.00	Supplying and drawing following sizes of FRLS/HFFR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 4 sq. mm	40.00	Meter	220.00	8800.00
1.02	6 x 6 sq. mm	15.00	Meter	635.00	9525.00
2.00	Supply and fixing of 32 x 20 mm DLP mini-trunking white-system with independent cover etc. as required complete.	10.00	Meter	329.00	3290.00
3.00	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
3.01	End cap	1.00	Nos.	188.00	188.00
3.02	internal / external angle	4.00	Nos.	176.00	704.00
3.03	changeable flat angle	2.00	Nos.	217.00	434.00
3.04	flat junction	1.00	Nos.	354.00	354.00
4.00	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
4.01	15/16 A switch	8.00	No.	174.00	1392.00
4.02	6 pin 15/16 A socket outlet	8.00	No.	217.00	1736.00
5.00	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
5.01	6 Module	4.00	No.	205.00	820.00
6.00	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
6.01	6 Module	4.00	Nos.	387.00	1548.00
7.00	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
7.01	Triple pole 5 A to 32 A	2.00	Each	1059.00	2118.00
7.02	Triple pole and neutral 5 A to 32 A	2.00	Each	1288.00	2576.00

8.00	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	2.00	Nos.	1098.00	2196.00
9.00	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
9.01	6 /10/16 Sq.mm.	24.00	Nos.	37.00	888.00
	Total Estimated Rs.(i/c GST)				36569.00
	Quoted Percentage Above /Below				
	Quoted Amount Rs.(i/c GST)				

Bidder Signature & Date

Bidder Seal


 ताल्लूरि केशवदास
 TALLURI KESAVADAS
 अधिशासी अभियंता (विद्युत)
 Executive Engineer (Elect)
 सं.वि.वि. भा.प्रौ. संस्थान, कानपुर
 I.W.D., I.I.T. Kanpur
 3/3/66