

QUOTATION

Name of Work : Dismantling and refixing of solar panels, solar cables, GI Earthing strip etc. with other associated works.

Sl. No.	Item Description	Qty.	Units	Rate	Amount
1	Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, G.I. tube, having single prong at top, with 85 mm dia 6 mm thick G.I. base plate including holes etc. complete as required.	1.00	Each	603.00	603.00
2	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	50.00	Meter	284.00	14200.00
3	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.				
(a)	25 mm	20.00	Meter	167.00	3340.00
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
(a)	Cement mortar 1:6 (1 cement : 6 coarse sand)	0.09	cum	6939.68	624.57
5	Providing 15mm thick cement plaster of mix 1:4 (1 cement : 4 fine sand) at all levels.	0.33	sqm	388.66	128.26
6	Dismantling and refixing of existing solar panels with complete electrical connections as required.	30.00	Each	2490.00	74700.00
7	Supplying and fixing 32 mm dia, G.I. pipe (medium class) as required.	3.00	Meter	484.00	1452.00
8	Supplying & drawing following sizes of Flexible Tinned Copper Conductor/ Cross linkable (E Beam) LSZH Insulation/ Cross linkable (E Beam) LSZH Sheathed DC Solar Cable as reqd.				
(a)	4.0 sq.mm	3.00	Meter	148.00	444.00
(b)	6.0 sq.mm	3.00	Meter	212.00	636.00
	Total Rs.				96,127.83
	Total stimated Rs. (i/c GST)				96,128.00
	Quoted Percentage Above /Below				
	Quoted Amount Rs. (i/c GST)				

Bidder Signature & Date

Bidder Seal


 30.09.2026
प्रदीप कुमार
 (PRADEEP KUMAR)
 अधीनस्थ अभियंता (वि.), EE (Elect.)
 विद्युत विभाग, (Elect. Divn.)
 सं 0 नि 0 वि 0, मा 0 प्र 0 संस्थान कानपुर
 I.W.D., I.I.T. Kanpur-16