

QUOTATION

Name of work: Providing 3 nos. Copper Chemical earthing in WL Ext. -101 in Academic area as per requested by User with all allied works as required in the campus at IIT Kanpur.

| S. No. | Description | Qty. | Unit | Rate | Amount (Rs.) |
|--------|---|-------|-------|----------|--------------|
| 1 | Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. | | | | |
| a) | 3 x 4 sq. mm | 5.00 | Metre | 213.13 | 1065.67 |
| b) | 6 x 6 sq. mm | 1.00 | Metre | 618.71 | 618.71 |
| 2 | Supply and fixing of 32 x 20 mm DLP mini-trunking white-system with independent cover etc. as required complete. | 3.00 | Mtr | 225.55 | 676.65 |
| 3 | Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system. | | | | |
| a) | End cap | 2.00 | Nos. | 147.95 | 295.91 |
| b) | internal / external angle | 2.00 | Nos. | 140.71 | 281.42 |
| c) | changeable flat angle | 1.00 | Nos. | 118.98 | 118.98 |
| d) | flat junction | 1.00 | Nos. | 140.71 | 140.71 |
| 4 | S & F following size of steel flexible pipe along with the accessories on surface etc as required | | | | |
| a) | 25 mm | 1.00 | Mtr | 85.87 | 85.87 |
| b) | 32 mm | 1.00 | Mtr | 99.32 | 99.32 |
| 5 | Chemical Earthing with Copper bonded rod of copper coating of 250 microns of dia 50 mm, length 3 Mtr with clamp, including earth enhancement material and RCC precast Pit cover and earthing pit etc as reqd. complete. | 3.00 | No. | 11865.18 | 35595.55 |
| 6 | Providing and fixing 25 mm X 5 mm copper strip in 40 mm dia G.I. pipe from earth electrode including connection with brass nut, bolt, spring, washer excavation and re-filling etc. as required. | 15.00 | Metre | 1604.72 | 24070.76 |

| S. No. | Description | Qty. | Unit | Rate | Amount (Rs.) |
|--------|---|-------|-------|---------|--------------|
| 7 | Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required. | 70.00 | Metre | 1202.24 | 84157.12 |
| 8 | Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required | | | | |
| a) | 50 mm dia | 5.00 | Metre | 676.65 | 3383.25 |
| | Total Estimated Rs.(i/c GST) | | | | 150589.93 |
| | Say Rs. | | | | 150590.00 |
| | Quoted percentage Above / Below | | | | |
| | Quoted Amount Rs.(i/c GST) | | | | |

Bidder Signature & Date

Bidder Seal

विनाय कुमार टिवारी
(VINAY KUMAR TIVARI)
अर्थात् अमेया (टी.) P.F. (कालापुर, ज.)
स.सि.टि., माधोपुर रास्ता, कालापुर
(W.B.), भारत