


QUOTATION

Sub:- Providing and making additional 5Amp & 15 Amp power points in common area of new barrack to accommodate more guards.

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 1.5 sq. mm	60.00	Metre	98.29	5897.41
1.02	3 x 2.5 sq. mm	80.00	Metre	141.74	11339.59
1.03	3 x 4 sq. mm	35.00	Metre	213.13	7459.71
2.00	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	85.00	Meter	225.55	19171.77
3.00	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
3.01	End cap	6.00	Nos.	147.95	887.72
3.02	internal / external angle	16.00	Nos.	140.71	2251.36
3.03	changeable flat angle	10.00	Nos.	118.98	1189.83
3.04	flat junction	5.00	Nos.	140.71	703.55
4.00	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
4.01	5/6 A switch	56.00	No.	106.57	5967.77
4.02	3 pin 5/6 A socket outlet	56.00	No.	126.23	7068.62
5.00	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
5.01	3 Module	4.00	No.	156.23	624.92
5.02	6 Module	26.00	No.	188.30	4895.89
6.00	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
6.01	3 Module	4.00	Nos.	341.43	1365.72
6.02	6 Module	26.00	Nos.	386.95	10060.78
	Total Estimated Rs.(i/c GST)				78884.63
	Say Rs.				78885.00
	Quoted Percentage Above /Below				
	Quoted Amount Rs.(i/c GST)				

Bidder Signature & Date

Bidder Seal


विनय कुमार तिवारी
(VINAY KUMAR TIWARI)
अधीक्षण अभियंता (वि.) SE (Electrical)
सं.नि.वि., मा० प्रौ० संस्थान, कानपुर
I.W.D., I.I.T., Kanpur