

QUOTATION

Name of Work: Installation of New Telephone point in Type-1 residence 144, 145, 146, 147, 148, 177, 178, 179, 180, 181, 182, 183, 184, 190, 1089, 1090, 1091, 1092, GH-1, Health Centre, VH and elsewhere in Campus of IIT Kanpur.

Sl. No.	Item Description	Qty	Units	Rate	Amount
1	Supplying and drawing following pair 0.5 sq mm FR PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.1	2 Pair	1298.16	Metre	39.32	51038.49
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
2.1	Telephone socket outlet	30.00	Each	153.13	4593.77
3	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required.				
3.1	1 or 2 Module (75mmX75mm)	10.00	Each	308.32	3083.21
4	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	5.00	Meter	225.55	1127.75
5	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
5.1	End cap	4.00	Nos.	147.95	591.81
5.2	internal / external angle	8.00	Nos.	140.71	1125.68
5.3	changeable flat angle	1.00	Nos.	118.98	118.98
5.4	flat junction	6.00	Nos.	140.71	844.26
6	Supply and fixing of 25 mm X 16 mm PVC casing and capping on surface as reqd.	60.00	Metre	83.81	5028.32
	Total Estimated Rs (i/c GST)				67552.28
	Say Rs.(i/c GST)				67552.00
	Quoted Percentage Above / Below				
	Quoted Amount Rs (i/c GST)				

Bidder Signature & Date

Bidder Seal

(Signature)
28/01/26
TALLURI KESAVADAS
अभियंता (विद्युत)
Executive Engineer (Elect)
स.पि.वि. मा.प्र. विभाग, कानपुर
L.V.D., I.I.T. Kanpur