

QUOTATION

Sub:-	Providing input & output points for UPS & its distribution in room with allied works in WL-210C and Providing copper earthing with strip for instruments in R-304 NL-II.				
SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
1.01	3 x 4 sq. mm	55.00	Metre	213.13	11722.40
1.02	2 x 10 sq.mm.	10.00	Meter	343.50	3434.98
2.00	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	23.00	Meter	225.55	5187.65
3.00	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
3.01	End cap	3.00	Nos.	147.95	443.86
3.02	internal / external angle	8.00	Nos.	140.71	1125.68
3.03	changeable flat angle	4.00	Nos.	118.98	475.93
3.04	flat junction	1.00	Nos.	140.71	140.71
4.00	S & F following size of steel flexible pipe along with the accessories on surface etc as required				
4.01	25 mm	12.00	Meter	85.87	1030.50
5.00	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	1.00	Nos.	1044.98	1044.98
6.00	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
6.01	Single pole 5 A to 32 A	2.00	No.	264.87	529.73
6.02	Double pole 5 A to 32 A	1.00	No.	678.72	678.72
7.00	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required.				
7.01	200 mm X 250 mm X 75 mm deep	1.00	No.	504.90	504.90
8.00	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
8.01	15/16 A switch	4.00	No.	125.19	500.76
8.02	6 pin 15/16 A socket outlet	4.00	No.	141.74	566.98
9.00	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
9.01	15/16 A switch	3.00	No.	161.40	484.21
9.02	6 pin 15/16 A socket outlet	3.00	No.	203.82	611.47

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
10.00	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
10.01	3 Module	1.00	No.	156.23	156.23
10.02	6 Module	1.00	No.	188.30	188.30
11.00	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
11.01	3 Module	1.00	Nos.	341.43	341.43
11.02	6 Module	1.00	Nos.	386.95	386.95
12	Supplying and Fixing following size angle iron in required shape and size i/c cutting, welding, painting etc. as reqd.				
12.01	35 x 35 x 5 mm	2.00	Mtr.	390.06	780.11
13.00	Chemical Earthing with Copper bonded rod of copper coating of 250 microns of dia 25 mm, length 3 Mtr with clamp, including earth enhancement material and RCC precast Pit cover and earthing pit etc as reqd. complete.	1.00	No.	11865.18	11865.18
14.00	Providing and fixing 25 mm X 5 mm copper strip in 40 mm dia G.I. pipe from earth electrode including connection with brass nut, bolt, spring, washer excavation and re-filling etc. as required.	10.00	Metre	1604.72	16047.17
15.00	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.	15.00	Metre	1202.24	18033.67
16.00	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
16.01	6 /10/16 Sq.mm.	4.00	Nos.	36.21	144.85
	Total				76427.37
	Total Estimated Rs.(i/c GST)				76427.00
	Quoted Percentage Above /below				
	Quoted Amount Rs (i/c GST)				

Bidder Signature & Date

Bidder Seal

T. Kesavadas
17/2/24

तल्लूरि केशवदास
TALLURI KESAVADAS
अधिव्यापी अभियंता (विद्युत)
Executive Engineer (Elect)
न.सि.वि. भा.पी. संस्थान, काणपुर
I.W.D., I.I.T. Kanpur