

QUOTATION


Name of Work: Electrical maintenance work of RA tower , New SAC , Old sport complex , Main sport stadium and Antaragni Ground against Pingla complaints.

Sl. No.	Item Description	Qty	Units	Rate (i/c GST)	AMOUNT (i/c GST)
1	Supply and & fixing following <i>modular switch/socket on the existing modular plates & switch box</i> including connection but excluding modular plate etc. as reqd.				
1.1	15/16 Amp. one way switch	9.00	Nos.	161.40	1452.63
1.2	3 Pin 5/6 Amp. socket outlet	2.00	Nos.	126.23	252.45
1.3	6 Pin 15/16 Amp. socket outlet.	8.00	Nos.	203.82	1630.58
1.4	Modular Type Electronic Fan regulator	1.00	Nos.	381.78	381.78
2	S & F following size/module, GI box along with <i>modular base and cover</i> plate for modular switches in recess as required.				
2.1	1/2 module (1 or 2 module)	1.00	Nos.	308.32	308.32
2.2	3 module	5.00	Nos.	338.33	1691.63
2.3	4 module	2.00	Nos.	354.88	709.76
2.4	6 module	2.00	Nos.	415.92	831.85
2.5	12 module	1.00	Nos.	565.94	565.94
3	Supply, Installation, Testing and commissioning LED light fittings integrated (with lamps) including connection, nut bolts, washer and screw etc. after removing old complete as required.				
3.1	LED light fitting 20 watt with PC-Batten, Crompton or approved Make	1.00	Nos.	427.30	427.30
3.2	LED <i>Ceiling Light 6 watt FR-plastic housing</i> (round/square shape), Crompton or approved make	5.00	Nos.	777.01	3885.05
3.3	LED <i>Ceiling Light 12 watt FR-plastic housing</i> (round/square shape), Crompton or equivalent approved make	17.00	Nos.	1000.49	17008.35
4	Supply, Fixing, Testing and commissioning of following LED Tubes and lamps in existing old fittings including connection etc. complete as required.				
4.1	LED PC Tube rod 20 watt, 4 ft long, T8, double/single sided inbuilt driver (Make Crompton or as per approved make)	35.00	Nos.	346.60	12131.08
5	Supply, Installation, Testing and commissioning LED Street and flood light fitting of following rating make up of pressure die aluminium housing with PC cover of following protection complete with all accessories including rag bolts with washer etc as reqd.				

Sl. No.	Item Description	Qty	Units	Rate (i/c GST)	AMOUNT (i/c GST)
5.1	LED Flood light fitting 120 watt, =>110lm/w,IP66, (Make_ Crompton_(CatNo.LFLN-120-CDL/60-M) or approved equivalent make).	1.00	Nos.	10454.98	10454.98
5.2	LED Flood light fitting 200 watt, =>110lm/w,IP66, (Make_ Crompton_(CatNo.LFLN-200-CDL/60-M) or approved equivalent make).	5.00	Nos.	16575.87	82879.35
	Total Rs.(i/c GST)				134611.05
	Total Estimated Rs.(i/c GST)				1,34,611.00
	Quoted percentage Above/Below				
	Quoted Amount Rs.(i/c GST)				

Bidder Signature & Date

Bidder Seal


 TALLURI KESAVADAS 25/3/26
 अधिशाही अभियंता (विद्युत)
 Executive Engineer (Elect)
 च.वि.वि. वा.प्रौ. संस्थान, कानपुर
 I.W.D., I.I.T. Kanpur