

QUOTATION

Name of Work: Electrical maintenance work of Hall-6 (GH-Tower), Hall-8, Hall-9, Hall-12, Hall-14, VH-1,2 and SIDBI Extension against Pingla complaints.

Sl. No.	Item Description	Qty	Units	Rate (i/c GST)	AMOUNT (i/c GST)
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor single core cable in / on the existing surface / recessed, PVC / steel conduit as reqd.				
1.1	3 x 1.5 Sq.mm..	66.50	Mtr.	98.29	6536.30
1.1	3 x 4 Sq.mm..	32.00	Mtr.	213.13	6820.31
1.2	6 x 4 Sq. mm.	12.50	Mtr.	409.72	5121.44
2	Supply and & fixing following modular switch/socket on the existing modular plates & switch box including connection but excluding modular plate etc. as reqd.				
2.1	5/6 Amp one way switch	41.00	Nos.	106.57	4369.26
2.2	15/16 Amp. one way switch	16.00	Nos.	161.40	2582.45
2.3	3 Pin 5/6 Amp. socket outlet	27.00	Nos.	126.23	3408.08
2.4	6 Pin 15/16 Amp. socket outlet.	13.00	Nos.	203.82	2649.70
2.5	Modular Type Electronic Fan regulator	3.00	Nos.	381.78	1145.34
2.6	Modular type blanking plate.	4.00	Nos.	41.39	165.54
3	S & F following size/module, GI box along with modular base and cover plate for modular switches in recess as required.				
3.1	1/2 module (1 or 2 module)	3.00	Nos.	308.32	924.96
3.2	4 module	6.00	Nos.	354.88	2129.28
3.3	6 module	7.00	Nos.	415.92	2911.46
3.4	8 module	2.00	Nos.	469.72	939.45
3.5	12 module	1.00	Nos.	565.94	565.94
4	S & F following size modular base and cover plate for following modular metal boxes etc as required.				
4.1	3 module	2.00	Nos.	156.23	312.46
4.2	4 module	2.00	Nos.	163.47	326.94
4.3	6 module	1.00	Nos.	188.30	188.30
4.4	12 module	2.00	Nos.	281.42	562.84
5	S & F MCB of following pole and rating 240/415 volts 'C' series in the existing MCB DB complete with connection, testing & commissioning etc as reqd. (legrand)				
5.1	Single Pole 6 amp to 32 amp	2.00	Nos.	294.87	589.74
5.2	Single Pole & Neutral 6 amp to 32 amp	1.00	Nos.	665.27	665.27

Sl. No.	Item Description	Qty	Units	Rate (i/c GST)	AMOUNT (i/c GST)
6	Supplying and fixing 20 amps 415 volts, TPN industrial type, socket outlet with 4 pole earthing metal enclosure, metal plug top, along with 20 amps, 10 KA, TP MCB on surface or in recess with chained cover for the socket outlet and complete as reqd.	1.00	Nos.	2679.70	2679.70
7	Supply, Installation, Testing and commissioning LED light fittings integrated (with lamps) including connection, nut bolts, washer and screw etc. after removing old complete as required.				
7.1	LED light fitting 20 watt with PC-Batten, Crompton or approved Make	12.00	Nos.	427.30	5127.65
7.2	LED light fitting (Integrated) 36/40 watt (surface/suspended type) , 300X1200 mm; approved Make.	1.00	Nos.	5396.65	5396.65
7.3	LED Ceiling Light 6 watt FR-plastic housing (round/square shape), Crompton or approved make	19.00	Nos.	777.01	14763.19
7.4	LED Ceiling Light 12 watt FR-plastic housing (round/square shape), Crompton or equivalent approved make	11.00	Nos.	1000.49	11005.40
8	Supply, Installation, Testing and commissioning LED Street and flood light fitting of following rating make up of pressure die aluminium housing with PC cover of following protection complete with all accessories including rag bolts with washer etc as reqd.				
8.1	LED Street light fitting 25 watt (Bracket type), =>100lm/w, IP65 . (Make_Crompton cat LSTS-25-CDL-M).	1.00	Nos.	2298.96	2298.96
9	Supply, Fixing, Testing and commissioning of following LED Tubes and lamps in existing old fittings including connection etc. complete as required.				
9.1	LED Picture/candle lamp 10 watt pin/screw (E14/E27/B22 type) (Make_Havells, Philips or approved make)	2.00	Nos.	209.00	417.99
10	Supply, Fixing, Testing and commissioning of following LED Tubes and lamps in existing old fittings including connection etc. complete as required.				
10.1	LED PC Tube rod 20 watt, 4 ft long, T8, double/single sided inbuilt driver (Make_Crompton or as per approved make)	43.00	Nos.	346.60	14903.90
11	1-phase Astronomical Timer Switch complete as reqd. Make_Lauritz Knudsen Astro Pro Cat No. AS2DCDS or equivalent Approved make.	2.00	Nos.	5753.60	11507.20
12	Supply and fixing of 32 x 12.5 mm DLP mini-trunking white-system with independent cover etc. as required complete.	56.00	Meter	171.75	9617.96

Sl. No.	Item Description	Qty	Units	Rate (i/c GST)	AMOUNT (i/c GST)
13	Supply and fixing of following accessories suitable for 32 mm x 12.5 mm size plastic trunking white system.				
13.1	End cap	5.00	Nos.	74.49	372.47
13.2	internal / external angle	8.00	Nos.	103.46	827.71
13.3	changeable flat angle	8.00	Nos.	111.74	893.92
13.4	flat junction	6.00	Nos.	140.71	844.26
14	Supply and fixing of 32 x 20 mm DLP mini-trunking white-system with independent cover etc. as required complete.	12.00	Meter	225.55	2706.60
15	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
15.1	End cap	2.00	Nos.	147.95	295.91
15.2	internal / external angle	2.00	Nos.	140.71	281.42
15.3	changeable flat angle	2.00	Nos.	118.98	237.97
15.4	flat junction	2.00	Nos.	140.71	281.42
16	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
16.1	End cap	5.00	Nos.	185.20	926.00
17	Supply, fixing, testing & commissioning MCB of following pole and rating 240/415 volts 'C' curve 10kA in the existing MCB DB complete as reqd. (legrand or approved Make)				
17.1	Single Pole & Neutral 40 amp to 63 amp	1.00	Nos.	1103.95	1103.95
18	Supply, Fixing, Testing and commissioning of following LED Tubes and lamps in existing old fittings including connection etc. complete as required.				
18.1	Triple pole & Neutral 40 amp to 63 amp	1.00	Nos.	2019.61	2019.61
	Total Rs. (i/c GST)				131424.89
					131425.00
	Quoted Percentage Above /Below				
	Quoted Amount Rs. (i/c GST)				

Bidder Signature & Date

Bidder Seal

T. K. Cauda
27/03/26

ताल्लुरि केशवदास
TALLURI KESAVADAS
अधिसायी अभियंता (विद्युत)
Executive Engineer (Elect)
स.नि.वि. भा.प्रौ. संस्थान, कावपुर
I.W.D., I.I.T. Kanpur