

## QUOTATION


**Sub:** Repairing and Replacement of defective electrical items in Rajeev Motwani building R. No. 101, NL-II-206B, Physics Work Shop-2, NCL-300, Low Speed Aerodynamics Lab, FB-667, Old Lecture Hall L-6, ACMS-210 Core Lab, Computer Center GF, and different labs and offices in academic area on complaint basis.

S.N.	Description	Qty.	Unit	Rate(Rs.)	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	1 X 1.5 Sq.mm	4.00	Mtr		
b	3 X 1.5 Sq.mm	18.00	Mtr		
c	3 X 2.5 Sq.mm	40.00	Mtr		
2	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a	25 x 16 mm	2.00	Mtr.		
3	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.	28.00	Mtr.		
4	S & F of following size of steel flexible pipe alongwith the accessories on surface etc as required.				
a	20 mm	2.00	Mtr.		
5	Supplying and fixing following rating, 240 volts, 'C' series, minature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc as reqd.				
a	Single Pole ( 5 Amp to 32 Amp )	1.00	Nos.		
b	Single Pole ( 40 Amp to 63 Amp )	1.00	Nos.		
6	Supply & retrofitting 18 watt LED PLL lamp in existing fitting and connection etc.as reqd	17.00	Nos.		
7	Supply & retrofitting 1 x 20 watt Tube LED lamp in existing fitting and connection etc.as reqd	21.00	Nos.		

S.N.	Description	Qty.	Unit	Rate(Rs.)	Amount
8	S/F, connecting, testing and commissioning 18 watt LED surface mounted luminaires with diffuser etc.as reqd.	21.00	Nos.		
9	Supply / fixing and connecting & commissioning following lamps in existing fitting as reqd.				
a	PL-c 18 watts	21.00	Nos.		
10	Alteration of internal wiring in existing fitting of any type for retrofitting of tube LED i/c dismantelling & refixing as reqd.	32.00	Nos.		
11	Supplying and fixing following piano type switch/socket on the existing switch box/cover including connections etc as reqd.				
a	5/6 amps switch	2.00	Nos.		
b	5 pin 5/6 amps socket outlet	2.00	Nos.		
12	Supplying and fixing following modular switch/socket on the existing modular plate & switch box/ DLP plastic trunking including connections but excluding modular plate etc as reqd.				
a	5/6 amps switch	13.00	Nos.		
b	15/16 amps switch	8.00	Nos.		
c	3 pin 5/6 amps socket outlet	8.00	Nos.		
d	6 pin 15/16 amps socket outlet	8.00	Nos.		
13	Supplying and fixing following Modular GI/plastic base & cover plate on existing modular metal boxes/DLP plastic trunking etc. as required.				
a	1 or 2 Module	1.00	Nos.		
b	3 Module	1.00	Nos.		
c	6 Module	4.00	Nos.		
d	12 Module	2.00	Nos.		
14	Supplying and fixing following Module Plastic box for fixing modular switches/sockets in surface/recess etc as required.				

S.N.	Description	Qty.	Unit	Rate(Rs.)	Amount
a	1 or 2 Module	1.00	Nos.		
b	3 Module	1.00	Nos.		
c	6 Module	4.00	Nos.		
d	12 /16 Module	2.00	Nos.		
15	Supply fixing connecting & commissioning 3 pin metal enclosed plug top 20 Amp. as reqd.	1.00	Nos.		
16	Supply fixing connecting & commissioning 3 pin metal clade socket 20 Amp. as reqd.	1.00	Nos.		
17	Drawing of computer network cable/ PVC insulated flexible cooper/ Aluminium single core cable of size 1.5sqmm to 25 sqmm/ telephone cable upto 10 pair in existing pipe / casing and capping as reqd including numbering the wires at both the ends.	60.00	Mtr.		
18	Dismantling & refixing DB/TPN Switches upto 100A/ loose wire boxes/ M.S. boxes alongwith all accessories etc as reqd.	10.00	Nos.		
19	Dismantling of ceiling fan / rally fan / all type fitting without regulator I/c depositing in store etc as reqd.	21.00	Nos.		
20	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	100.00	Sq.in.		
21	Locating fault in wiring rectifying moving & restoring supply the same & making good the damages etc as reqd.	23.00	Nos.		

**Total Rs.**

  
 राघवेंद्र सिंह  
 RAGHVENDRA SINGH  
 अधिष्ठाता अभियंता (वि.) E.E. (Elect.)  
 राजकीय आरपीएड अखण्ड, कानपुर  
 I.W.E., I.I.T., Kanpur  
