


QUOTATION

Sub: Replacement of damaged 50 pairs telephone cable near Drawing Hall building.

S.N.	Description	Qty.	Unit	Rate	Amount
1	Supplying and embedding following dia G.I. pipe (medium class) in pole collar/ foundation (during casting) for cable entry including bending the pipe to the required shape complete as required.				
a	40 mm dia	6.00	Mtr		
2	S&L, connecting and commissioning following 50 pairs (0.5mm) jelly filled armoured telephone cable PVC insulated and PVC sheathed annealed tinned copper conductor.				
a	In ground	42.00	Mtr		
b	Laying direct in open duct	4.00	Mtr		
c	Laying direct in pipe	6.00	Mtr		
3	Fixing of telephone DP upto 100 pair from wall / floor i/c repairing good the same as required.	3.00	Nos		
4	Digging cable trench, lifting brick/s and cable for locating fault and refilling the trench, ramming & making good the same as reqd.	10.00	Mtr		

Total Rs.


राघवेंद्र सिंह
RAGHVENDRA SINGH
अधिराजी अधिरयता (वि०) E.E. (Elect.)
संनिकवि०, भारतीय संस्थान, कानपुर
I.W.D., I.I.T., Kanpur
See