


QUOTATION

Name of work - Repairing and descaling of solar water heating system installed on roof top of E, F Block and Mess of Hall-12.

S. No	Description of Items	Qty	Unit	Rate	Amount
1	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.				
a	20mm dia	20.00	mtr		
2	Descaling of solar hot water panel of 100 LPD capacity including disconnecting/ dismantling solar panel descaling with descalant and re-connecting panel with associated repair,gasket,ss nut and bolts etc. complete as required.	80.00	Nos.		
3	S & F connecting & commisioning of SS Socket Welding 20 mm as reqd.	2.00	Nos.		
4	Supplying and fixing of 1"x6" size with 304 grade SS nipple in hot water tank.	2.00	each		
5	Painting two coat of solar hot water complete system including collector stand,hot water storage and makeup tank stands, pipe sports after cleaning the surface with sand paper / cloth etc as reqd.	80.00	Nos.		

Total Rs.


राघवेंद्र सिंह
RAGHVENDRA SINGH
अधिकाारी अभियंता (वि.) E.E. (Elect.)
संविधि: वायवीय संस्थान, कानपुर
I.W.D., I.I.T., Kanpur