


## QUOTATION

**Sub: Modification & renovation in office of HOD civil Engineering FB-312.**

S.No.	Name of Work	Qty.	Unit	Rate	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	3 X 2.5 Sq.mm	50.00	Mtr		
b	3 x 4 Sq.mm	35.00	Mtr		
2	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as reqd.				
a	25 mm	35.00	Mtr		
3	S & F of following size of steel flexible pipe alongwith the accessories on surface etc as required.				
a	25 mm	2.00	Mtr.		
4	Supplying and fixing following of size/modules, GI box along with modular base & cover plate for modular switches in recess etc as reqd.				
a	1 or 2 module (75mm x 75mm)	2.00	Nos.		
b	3 module (100mm x 75mm)	2.00	Nos.		
c	4 module (125mm x 75mm)	2.00	Nos.		
d	6 module (200mm x 75mm)	8.00	Nos.		

S.No.	Name of Work	Qty.	Unit	Rate	Amount
5	Supplying and fixing following modular switch/socket on the existing modular plate & switch box/ DLP plastic trunking including connections but excluding modular plate etc as reqd.				
a	5/6 amps switch	16.00	Nos.		
b	15/16 amps switch	4.00	Nos.		
c	3 pin 5/6 amps socket outlet	16.00	Nos.		
d	6 pin 15/16 amps socket outlet	4.00	Nos.		
e	Blanking Plate	1.00	Nos.		
6	Supplying and fixing 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 amps "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	2.00	Nos.		
7	S & F following rating modular RJ-11 telephone jack (1M) complete with modular box i/c modular base & cover plate etc as reqd.	2.00	Nos.		
8	Fixing, Internet Box of size 75mm x 75mm x 40 mm including brass screw on surface / recessed as reqd.	4.00	Nos.		
9	Supplying and drawing following pair 0.5 Sq.mm FRLS PVC insulated copper conductor, unarmoured telephone cable in the existing surface/recessed steel/PVC conduit as reqd.				

S.No.	Name of Work	Qty.	Unit	Rate	Amount
a	2 Pair	90.00	Mtr		
10	Drawing of computer network cable/ PVC insulated flexible cooper/ Aluminium single core cable of size 1.5sqmm to 25 sqmm/ telephone cable upto 10 pair in existing pipe / casing and capping as reqd including numbering the wires at both the ends.	200.00	Mtr.		
<b>Total Rs.</b>					

  
 राघुएन्द्र सिंह 3/11/18  
 RAGHENDRA SINGH  
 अधिकारी (अ.क.) (वि.प.) E.E. (Direct)  
 संचालनालय, कोयंबूर शहर, कोयंबूर  
 W.D. (I.T. R. 1000)  
